
# Air leakages through cross laminated timber (CLT) constructions

Hans Boye Skogstad, M. Sc. 1 Lars Gullbrekken, M.Sc. 1 Kristine Nore, Ph.D. 2 1 SINTEF Building and Infrastructure, Norway 2 Moelven MassivTre AS, Norway







#### Intro


- Laboratory measurements
- Objective: Measure the airtightness of a cross laminated timber construction with both wall and floor elements.
- Measurements are conducted to evaluate the need of separate wind- and/or vapour barrier in cross laminated timber constructions.
- Test results are used to evaluate the need of a separate air barrier in cross laminated timber constructions in order to fulfil the Norwegian requirements regarding air tightness (n<sub>50</sub>).




# Method

- The resistance to penetration of air through the CLT wall-floor-wall construction is measured according to NS-EN 12114 Thermal performance of buildings. Air permeability of building components and building elements. Laboratory test methods.
- The air leakages are measured at 50 Pa pressure difference over the test section.
- Airtightness measurements performed at delivery moisture content of 14 kg/kg and after drying to <10 kg/kg.
- The measurements are performed in the air permeability chamber located at SINTEF Building and Infrastructure in Trondheim.

















# Two different wall elements with and without gluing of the board edges












#### Two different test sections




## Test performance





10

#### Test results





Test section	Moisture content kg/kg	Influence on the buildings air change rate h <sup>-1</sup>
Board edges not glued	~ 0.14	2.9
	< 0.10	7.7
Board edges glued	~ 0.14	1.8
	< 0.10	2.8



## Discussion

- Air leakage through the CLT construction can vary depending on the moisture content.
- The measurements support the recommendation that CLT constructions need to be designed with airtight joints.



